Highway 401 Cornwall Centre Road Overpass

Rapid Bridge Replacement GWP 4029-08-00

Presentation on Methodology of Rapid Bridge Replacement For a Concrete Rigid Frame Structure

April 2016





PRESENTATION OVERVIEW



- BACKGROUND
- **WEST BOUND LANE SEGMENTAL APPROACH**
- **► EAST BOUND LANE SINGLE PIECE WITH FOOTINGS**
- LESSONS LEARNED








BACKGROUND




- Location
- History
- Design Criteria




LOCATION











EXISTING STRUCTURE





MEDIAN RETAINING WALL

EXISTING STRUCTURE





GENERAL HISTORY



- Original twin structures built in 1962
- Single span steel girder with composite concrete deck superstructures
- Conventional concrete abutments on spread footings
- ▶ 51.5° skew
- West median retaining wall leaning
- West median retaining wall tied back to deadman anchor in 2009
- Decision made to replace in 2011 following EA

DESIGN CRITERIA



- Highway 401
 - ► 2.5m Left Shoulder
 - ► Two 3.75m Lanes
 - ► 3.0m Right Shoulder
 - ▶ PL-3 (TL-5) Concrete Barriers
 - ▶ 51.5° skew
 - 600m horizontal radius
 - ► 2.4% superelevation
 - ► AADT = 23,000
 - ▶ 48% Trucks
 - ▶ Peak VPH = 3300

DESIGN CRITERIA




- Cornwall Centre Road
 - ▶ 1.8m multi-use path
 - ▶ 0.5m Curb and Gutter
 - ▶ 3.6m SBL
 - ▶ 3.6m NBL
 - ▶ 0.5m Curb and Gutter
 - ▶ 1.8m multi-use path
 - Sag profile (lowest point at WBL)

* Original road had sidewalk on one side only. Shift in centerline to accommodate new symmetrical section.


CONFIGURATION






CONFIGURATION





CONFIGURATION





PRESENTATION OVERVIEW



WEST BOUND LANE – SEGMENTAL APPROACH

- Engineering Challenges
- ► RBR Configuration for *Footing* Move
- ► RBR Configuration for *Rigid Frame* Move



WBL COMPONENTS TWO FOOTINGS + TOP RIGID FRAME




WBL ENGINEERING CHALLENGES



- Heavy Load (1100 tonnes top RF piece)
- Load concentrated at obtuse corners
- Short structure span limits space for SPMT's
- Legs deflect outward when lifted
- Road profile sag curve set maximum length of SPMT train (could not lower road)
- Lateral earth pressure due to heavy axle loads higher than friction at underside of footing
- How to construct joint / tolerances (24 m long mating section)


TRANSPORT ROUTES





WBL MEDIAN CROSS-OVER






WBL MEDIAN CROSS-OVER






WBL STAGED CONSTRUCTION





WBL FOOTING
























WBL TEMPORARY FOUNDATION AT STAGING AREA



SPMT GRADE CHANGE LIMIT














WBL RIGID FRAME MOVE





Note: Dywidag Bars to restrain twist

WBL RIGID FRAME MOVE

























WBL RF MOVE





WBL COMPLETED JOINT





WBL – MODELING & ANALYSIS



Structural Modeling

- Software: CSiBridge Commercial Finite Element Analysis (ver.14)
- *Elements:* Concrete Rigid Frame 4-node quadrilateral shell element Lifting System – 2-node beam element


	Lifting System Section Properties				
Member	EBL I (m ⁴) A (m ²)		WBL		
			I (m ⁴)	A (m ²)	
SPMT	1.298x10 ⁻²	0.491	1.298x10 ⁻²	0.491	
Lifting Beam	1.615x10 ⁻³	0.037	-	-	
Jacking Tower	8.166x10 ⁻³	0.075	-	-	
Connecting Beam	7.991x10 ⁻²	0.136	7.991x10 ⁻²	0.136	

- Loading: Equal vertical force was applied to every SPMT axle location.
 - Total load applied to the axles is equal to the total weight of the concrete structure and the lifting system
- Boundary conditions: Fictitious boundary conditions at center of deck and lifting system for modeling stability (zero reactions)





Structural Modeling




Transport System Modeling – Beam Element

WBL – MODELING & ANALYSIS



Positioning of SPMT


 Place more axles of SPMT at obtuse corners to take more load from structure and to avoid excessive distortion (twisting) of the structure



LIFTING SYSTEM



SPMT Configuration








Reactions at Block-outs

Location	Reactions		
Location	Flexible	Infinite Stiffness	
Block-out 1 (Obtuse corner)	1954 kN	2400 kN	
Block-out 2	1545 kN	1250 kN	
Block-out 3 (Acute corner)	1557 kN	1400 kN	



WBL – Results


Deformations



	Displacements (mm)			
Location	x (perpendicular to centreline of CCR)	y (parallel to centreline of CCR)	z (vertical direction)	
Deck – Centre (Base Point)	0	0	0	
Deck – Obtuse Corner	0	0	10.8	
Deck – Acute Corner	1.3	-0.2	31.9	
Wall Base – Obtuse Corner	16.6	4.6	10.1	
Wall Base – Acute Corner	21.6	4.7	32.7	

WBL – Results






Moment and Shear (Demand & Capacity)		Critical Locations		
		Obtuse Corner (h=1000)	Obtuse Corner (h=750)	
	Demand	359	252	
Moment (kN-m)	Capacity	416	304	
()	C/D	1.16	1.21	
Shear (kN)	Demand	125	80	
	Capacity	1,055	817	
	C/D	8.44	10.21	

WBL DECK REINFORCING






TUL = TOP UPPER LAYER TML = TOP MIDDLE LAYER TLL = TOP LOWER LAYER

WBL DECK REINFORCING






WBL CONSTRUCTION JOINT



- Bar splice solved with headed bars
- Width of key needed to consider:
 - Theoretical leg deflection
 - Bowing of wall versus footing
 - Tilt of walls
 - Allowable construction tolerances
- Developed tight construction tolerances to ensure fit

WBL CONSTRUCTION JOINT









Dimensions	Tolerance
Width of key at top of wall of WBL footing component	+/- 3mm
Width of key (stem) at bottom of wall of WBL rigid frame component	+/- 3mm
Depth of key at construction joints	+/- 6mm
Length of key at bottom of key (wall of rigid frame component) and top of key (wall of footing component)	+/- 13mm
Insert or headed bar location along length of wall	+/- 13mm
Insert or headed bar location along width of wall	+/- 10mm
Distance between walls at key	+/- 6mm
Distance between walls at haunch	+/- 13mm
Plumb over height of walls of rigid frame component	+/- 6mm

WBL CONSTRUCTION TOLERANCES

No single tolerance was actually met during construction, but fit like a glove anyway

LESSON LEARNED

- The accumulation of maximum tolerances is unlikely (could consider relaxation of concrete dimensional tolerances)
- Bar placement to tight tolerances is achievable in the field (no conflicts with upper and lower headed bars)
- Model agreed closely with observed





► EAST BOUND LANE – SINGLE PIECE WITH FOOTINGS

- Engineering Challenges
- ► RBR Configuration for *Single Piece Rigid Frame* Move
- Equipment
- Modeling and Analysis



EBL - CONCRETE RIGID FRAME ONE PIECE





EBL - CONCRETE RIGID FRAME ONE PIECE




EBL ENGINEERING CHALLENGES



- Heavy Load (1400 tonnes)
- Load concentrated at obtuse corners
- Short structure span limits space for SPMT's
- Required to lower entire structure 1.5 m at destination (beyond jack stroke of SPMT's)
- Depth of lifting beam and SPMT equipment restricts space available of climbing jacks
- Structure deflects/twists when lifted

EBL – OVERVIEW











SPMT Configuration



EBL – LIFTING SYSTEM









SPMT – Kamag 2400ST



Technical data

Item	51000165		51000164	
Туре	K 2406 ST HS4E		K 2406 HS4E	
Tyre filling	PU-fil	ing	Air-filling 10 bar	
Speed	1 km/h	3 km/h	1 km/h	3 km/h
Payload	261,000 kg	213,000 kg	202,800 kg	186,000 kg
Admissible gross weight	288,000 kg	240,000 kg	228,000 kg	211,200 kg
Dead weight	27,000) kg	25,200 kg	
Admissible axle load	48,000 kg	40,000 kg	38,000 kg *)	35,200 kg
Platform dimensions	approx. 8,400 x 2,430 mm			
Coupling lentgh	approx. 8,400 mm			
Platform height driving position	approx. 1,490 mm			
Axle compensation	approx. +/- 350 mm			
Platform height lowered	approx. 1,140 mm			
Steering / steering angle	elektronical-hydraulical approx. + 1309-100°			
Number of wheel bogies / braked	12/6			
Wheel bogies driven	4			
Tractive force	240 kN			
Brake performance	240 kN			

*) max distance less than 300m, at 0.5 km/h and distance less than 300m: 40,000 kg


Climbing Jack – CS250








Structural Modeling



Concrete Rigid Frame Modeling – Shell Element



Transport System Modeling – Beam Element






Reactions at Block-outs

Location	Reactions		
Location	Flexible	Infinite Stiffness	
Block-out 1 (Obtuse corner)	2403 kN	2200 kN	
Block-out 2	1272 kN	1800 kN	
Block-out 3	1174 kN	1600 kN	
Block-out 4 (Acute corner)	2114 kN	1400 kN	





Deformations




	Displacements (mm)			
Location	x (perpendicular to centreline of CCR)	y (parallel to centreline of CCR)	z (vertical direction)	
Deck – Centre (Base Point)	0	0	0	
Deck – Obtuse Corner	0	0	10.6	
Deck – Acute Corner	1.1	-0.1	32.7	
Wall Base – Obtuse Corner	22.1	6.5	9.9	
Wall Base – Acute Corner	27.0	6.5	33.5	





Structural Capacity



Moment and Shear (Demand & Capacity)		Critical Locations		
		Obtuse Corner (h=1000)	Obtuse Corner (h=750)	
	Demand	381	256	
Moment (kN-m)	Capacity	416	304	
	C/D	1.09	1.19	
Shear (kN)	Demand	120	83	
	Capacity	1,055	817	
	C/D	8.79	9.84	



EBL - CONCRETE RIGID FRAME ONE PIECE



EBL - CLIMBING JACK





EBL - FINAL DESTINATION





EBL - RESTRAINT SYSTEM























































PRESENTATION OVERVIEW




LESSONS LEARNED

- ► Temporary RSS Wall
- Pressure Grouting
- Steel Forms
- Bearings at Lifting Points
- Skews/Twist
- ► Tie Bars

TEMPORARY RSS WALL






* 150mm AT MEDIAN RETAINING WALL FOOTINGS GRANULAR B TYPE III TO BE COMPACTED TO 95% SPMDD GRANULAR A TO BE COMPACTED TO 100% SPMDD



TEMPORARY RSS WALL



TEMPORARY RSS WALLS





Climbing jacks hydraulic pump failure caused RSS wall to sustain load for 24 hrs

Proved capable of withstanding heavy loads close to vertical edge



PRESSURE GROUTING

- Experienced contractor (skipped every other grout holes creating air pockets)
- Sufficient equipment (tried to use one grout pump for both sides of wall)
- Was grout strength attained before WBL rigid frame lift?
 (only needed low strength < 1 MPa)
- Cores for dowels detected voids
- Ensure test cores are done before backfilling AND BEFORE SETTING RIGID FRAME TOP PIECE ON IT!



STEEL FORMS

- Unyielding form at bearing of rigid frame legs unable to accommodate rotation when deck falsework removed
- Concrete cover on sides of male key spalled off





STEEL FORMS

- Unyielding form at bearing of rigid frame legs unable to accommodate rotation when deck falsework removed
- Concrete cover on inside of male keys spalled off





BEARINGS AT LIFTING POINTS

- Elastomeric bearing pads on top of steel beams shown on drawings, but were not installed at time of move
- Concrete cover on sides of pocket spalled off





BEARINGS AT LIFTING POINTS ARE NOT OPTIONAL





SKEWS AND TWIST

- Analysis assumed infinite stiffness are lifting points (inserted pin-roller in finite element model)
- Actual SPMT system and lifting beams are flexible
- Review with specialists during design did not address lifting system flexibility and impact on structure
- Consider CMGC procurement to have Engineer and Contractor work together (to devise system to suit Contractors equipment and beam stockpile)
- Consider maximum 20° skew to provide more uniform loading
- Have lifting analysis done before casting concrete (could have added more reinforcing to soffit to accommodate twist)



► TIE BARS

- Did not work as intended (sag in some bars remained after lifting while others straightened out)
- Practically impossible to align holes from one wall to the other wall. Binding in holes caused "S" shape deflection in bars
- Recommend pretensioning of bars be based on jack pressures instead of sag measurements ("S" shape was horizontal)
- Provide hinge connection in bars at interior faces of walls to address alignment problems
- Proved not needed with alternative configuration of SPMT's



WBL - TIME TO CONSTRUCT

- ▶ 39 days total
 - > 6 days shift traffic and demolition
 - > 6 days low performance RSS wall
 - > 13 days high performance RSS Walls and backfilling

EBL – TIME TO CONSTRUCT

- ► 34 days total
 - > 5 days less than WBL due to omission of construction joint
- PRECASTING AND PREPARATION OF MEDIAN CROSS-OVER
 - 80 days total

ACKNOWLEDGEMENTS



- AECON General Contractor
- MAMMOET Subcontractor For Heavy Lift Move
- SARENS Heavy Lift Specialist (Constructability Review)
- ALTON ASSOCIATES Temporary RSS Wall Design
- MORRISON HERSHFIELD Contract Administrator (Construction Photographs)
- ► Han Choi, Ph.D, P.Eng MMM Design Engineer
- Ying Yang, P.Eng MMM Checking Engineer
- MTO Angela Stewart, Project Manager (Design)
- MTO Mike DeLugt, Project Manager (Construction)



Questions?