

BRIDGE LATERAL MOVE TECHNOLOGY

Accelerated Bridge Construction (ABC)

U.S. Department of Transportation Federal Highway Administration

SLIDE-IN BRIDGE CONSTRUCTION (SIBC) FROM THE CONSTRUCTION/ CONTRACTOR'S PERSPECTIVE

December 15, 2015 at 11:00am MT



TARGET AUDIENCE: This training webinar was developed from the Construction/Contractor's perspective.

Today's Agenda:

>Welcome/Overview (~5 min.)

>Construction/Contractor's Perspective Presentation (~40 min.)

- >Question & Answer (~15 min.)
- >Next Steps (~3 min.)









Administrative items

- To join the audio, click the "Communicate" option from the menu bar and select either "Teleconference" (for phone) or "Audio Broadcast" (for "VOIP")
- Full screen view controls (bottom left corner of screen)
- During the webinar, please use Q&A box for questions (see panel on right side of WebEx screen)
 - Please direct questions to "All Panelists"
 - Submit your questions <u>throughout</u> the presentation
- If you have technical problems with the audio and/or visual portions of this webinar, please call 303-883-4811





DESIGN AND CONSTRUCTION OF THE I-5 SKAGIT RIVER BRIDGE REPLACEMENT

Max Kuney Christopher Vanek, PE

U.S. Department of Transportation Federal Highway Administration



DESIGN AND CONSTRUCTION OF THE I-5 SKAGIT RIVER BRIDGE REPLACEMENT








RFP Highlights

- Two Week Procurement
 - Project Approach
 - Schedule
 - Estimate



- Best Value = Price + Time + More Time
 - I-5 Closure = \$660,000 per 24 hours
 - Contract Time = \$50,000 per day





The Kuney/PB Pursuit Strategy

- High Priority: Minimize I-5 Closure
- Medium Priority: Minimize Contract Time
- Lower Priority: Low Construction Cost

WIN THE SCHEDULE! Our Goal: Less than 24 hour closure





Strategies to Minimize I-5 Closure

- Option 1: Construct on Land
 Roll in via I-5
- Option 2: Construct on Water

Float in on barges





Skid in on beams






Approach to Using Visualizations


Allows the team to:

- Plan the construction
- Identify critical path
- Verify construction tolerances



Three-Dimensional Modeling









Visualization of Alternatives

Floating Alternative



Skidding Alternative



Floating alternative initially selected






Design and Construction of the I-5 Skagit River Bridge Replacement

Schedule Review (Bid minus 4 days)

- Floating Operation Finalized
 - Significant infrastructure on barge
 - Variable water levels
 - Several risk items
- I-5 Closure: 24 to 48 hours














Revisit Skidding Alternative

- Less risk during move
- Challenge to construct everything during summer:
 - 68 temporary piles
 - 6 skid beams
 - New span

I-5 Closure: 12 to 24 hours



CENERAL CONTRACTORS

Structural Design Alternative Evaluation

• High Priority: Time to Construct

- Ability to complete during summer
- Accelerate if necessary

• Medium Priority: Total Weight

 Less than 915 tons = less risk during move and no remediation of existing substructure

Lower Priority: Cost





Initial Design Alternatives

Concrete Girders:

- Conventional girders
- Precast or CIP deck
- Steel Girders:
 - Twin girder systems (Inverset)[™]
 - Conventional girders
 - Precast or CIP decks
- Out of the Box:
 - Repair the truss
 - Permanent ACROW










Concrete Girder Alternatives

Advantages:

- Shorter fabrication time
- Ability to control schedule
- Conventional construction

Disadvantages:

- Span weight
 - Is 915 tons possible?
- Girder weight
 - Shipping and erection







Design and Construction of the I-5 Skagit River Bridge Replacement


Steel Girder Alternatives


Advantages:

- Lower span weight
- Lower girder weight
- Fewer beam lines
- Conventional construction

Disadvantages:

- Fabrication time
 - Does anyone have the plate?
 - Ability to fabricate immediately?
- Schedule
 - Fabricator on critical path









STRENGTH AND TRUST

Design Alternatives Evaluation (2 week procurement)

Concrete Alternatives:

- Week 1: Four initial concepts
- Week 2:


One concept refined

Steel Girder Alternatives:


Week 1: Three initial concepts
Week 2:

One concept refined

CONCRETE ALTERNATIVE SELECTED



Concrete Alternative Features



Lightweight Deck Girder Superstructure

- 9,000 psi mix
- 122pcf Concrete Weight Unit
- 133pcf Girder Unit Weight

Designed for Skidding

- Conventional bearing locations
- Temporary support at intermediate diaphragms

Other Unique Aspects

- Full moment girder connections
- Beam spacing accommodates ACROW pedestals


OMEGA MORGAN

Geometry control



Girder to Girder Connection

- Full flexural-shear transfer
- Eliminated girder line
- Reduced cracking potential







DMEGA MORGAN

Skidding System Features (three design days)





Construct Girders in Permanent Bearing Locations

- Two temporary bents
- Twelve 24" φ pipe bents
- Approx. 50' about mudline

Skid Track

- Located 20' from each end
- Facilitates ACROW removal
- Avoids conflict between temporary piles and existing piers
- 56-24" φ pipe piles

Heavy Trussed Beams

- Span 77' under ACROW
- Transfer new span in
- Transfer ACROW out







Bid Results

Summary

Three close bidders
Price within \$200,000
We won on technical score by \$700,000

	Skagit River Bridge - Permanent Bridge Replacement BEST VALUE DETERMINATION (ITP Section 4.5.1)		
	BEST VALUE EQUATION: ABV = \$P +	(SUM OF ALL TS)	CONTRACT: 8500 ENGINEER'S ESTIMATE: \$3,000,000 - \$10,000,000 UPSET AMOUNT: NA
	ABV = Apparent Best Value SP = The Proposal Price from the Price Proposal B-1 TS = Technical Score		Substantial Completion on or before Oct. 1, 2013
	Apparent Best Value (ABV) Technical Score (TS) 7,645,000 820,308.00 15,766,979 2,846,000.00	Proposal Price (\$P)	PROPOSER NAME
		6,825,000.00	Stands to set of the second
		12,926,979.00	
		6,875,800.00	Max J. Kuney Construction
	6,985,800 110,000.00	7,099,979.00	PROFESSION IN
	8,442,479	8,000,000.00	Example Calculation
	essful Proposal will be the one calculated to have the lower	Apparent Best Value	
PPARE	restul Proposal will be the one calculate to TH BEST VALUE DESIGN BUILDER NT 2ND BEST VALUE DESIGN BUILDER NT 3ND BEST VALUE DESIGN BUILDER NT 4th BEST VALUE DESIGN BUILDER	Max J, Kuney Construction	





DMEGA MORGA

Project Kickoff – NTP (June 19, 2013)

Design Activities

- Replacement Span Firsts:
 - WSDOT lightweight girder
 - Full moment girder connection
 - Span designed to be lifted 20' from ends
- Temporary Works:
 - Temporary bents
 - Skid beam bents
 - Elevation Control
 - Skid Beams

Design Delivery

- WSDOT over the shoulder reviews
- Shop drawings concurrent with design
- Design concurrent with construction







Temporary Works Design/Construction

Temporary Bents


- Adjacent to existing bridge
- Cantilevered condition
- 50' high above mudline

Skidding Bents

- Pile clusters to support main span
- Pile layout for other spans

Heavy Trussed Beams

- Span 77' under ACROW
- Other beam details







STRENGTH AND TRUST

Replacement Span Design/Construction

Lightweight Concrete Girders


- Day 2: Aggregate shipped
- Day 5: Final girder design and shop drawings commence simultaneously
- Day 20: Design RFC and shop drawings complete
- Day 22: First girder cast
- Day 37: Final girder cast







Project Timeline











OMEGA MORGAN

STRENGTH AND TRUS

Lifting Diaphragms

Skidding Support Condition

- Four point support
- Transition across skid beams

Design Details

- Weight an issue (915 tons)
- Reinforcement details







Precast Girder Construction









MEGA MORGAN

Temporary Pile Bents



Design and Construction of the I-5 Skagit River Bridge Replacement





OMEGA MORGAN

PRENGTH AND

Skidding Bents











Truss Beam



Design and Construction of the I-5 Skagit River Bridge Replacement





OMEGA MORGAN

STRENGTH AND

Set Prestressed Concrete Girders



Design and Construction of the I-5 Skagit River Bridge Replacement





EGA MORGAN

Girder Closure Pours



Design and Construction of the I-5 Skagit River Bridge Replacement





OMEGA MORGAN

Intermediate Diaphragms









MEGA MORGAN

Pour Concrete Barriers and Overlay








MEGA MORGAN

Prepare to move bridges








MEGA MORGAN

Design and Construction of the I-5 Skagit River Bridge Replacement

Move temporary ACROW bridges




Design and Construction of the I-5 Skagit River Bridge Replacement





DMEGA MORGAN

Move temporary ACROW bridges




Design and Construction of the I-5 Skagit River Bridge Replacement





MEGA MORGAN

One down, one to go...



Design and Construction of the I-5 Skagit River Bridge Replacement





OMEGA MORGAN

Ready to move new span










DMEGA MORGAN

Skid new span into place




GENERAL CONTRACTORS



OMEGA MORGAN

Design and Construction of the I-5 Skagit River Bridge Replacement

Skidding system












Moving the new span into place




Design and Construction of the I-5 Skagit River Bridge Replacement





DMEGA MORGAN

Lowering the new span into place










OMEGA MORGAN

Bridge in place










Add striping, clean up, and open







MEGA MORGAN

Bridge open to traffic







OMEGA MORGAN

Design and Construction of the I-5 Skagit River Bridge Replacement





Lessons Learned

- Examine the existing site conditions carefully
- Utilize As-Builts of the existing structure to look for conflicts
- Ensure critical materials are available to meet the schedule
- Ensure the local labor force can meet the needs of the project
- Federally funded projects have additional requirements
- Examine the risk transfer, especially in Design-Build





Bridge Slide Video

















COLORADO Department of Transportation



Q&A Panel

Max Kuney

President of Max J. Kuney Company

max@maxkuney.com

Phone no. 509.535.0651

Christopher M. Vanek, MSCE, PE

Senior Structural Engineer at Parsons Brinckerhoff

vanekcm@pbworld.com

Phone no: 813.520.4442









Websites/Resources

- SIBC Webinar Training Project Website
 - www.slideinbridgeconstruction.com
 - A recording of today's webinar, presentation slides, video, and Q&A results will be posted within 10 business days
- FHWA SIBC Representative
 - Mr. Jamal Elkaissi, Resource Center, Lakewood, CO
 - 720-963-3272
 - jamal.elkaissi@dot.gov
- FHWA SIBC Website
 - http://www.fhwa.dot.gov/construction/sibc/
 - SIBC Implementation Guide now available
 - Many other resources, case studies, etc. also available







SIBC Modules

- Web-based Training
 - 3 Modules: SIBC Part 1, Part 2, and Part 3
 - Each goes "live" with the associated webinars above
 - Module 3 will be available Friday, Dec. 18 at <u>http://slideinbridgeconstruction.com</u>









FIU ABC Center Training

NEXT WEBINAR:

Thursday, December 17, 2015 (1:00 – 2:00 pm Eastern)

"Industry Perspective on Precast Element Details for Successful ABC Projects"

To register, visit: http://www.abc-utc.fiu.edu

(earn one hour of PDH)

U.S. Department of Transportation Federal Highway Administration



COLORADO Department of Transportation



BRIDGE LATERAL MOVE TECHNOLOGY

Accelerated Bridge Construction (ABC)

U.S. Department of Transportation Federal Highway Administration

THANK YOU FOR YOUR PARTICIPATION!

For issues or questions regarding this training or the <u>www.slideinbridgeconstruction.com</u> website, please e-mail <u>sibc@aecom.com</u>

