




1


ABC Technologies Review


- ABC Definition: Accelerated Bridge Construction (ABC) is bridge construction that uses innovative planning, design, materials, and construction methods in a safe and cost-effective manner to reduce the onsite construction time that occurs when building new bridges or replacing and rehabilitating existing bridges. [AASHTO LRFD Guide Specifications for ABC, 1st Ed, 2018; https://www.fhwa.dot.gov/bridge /abc/; https://abc-utc.fiu.edu/resources/project-researchdatabases/project-database-keywords/]
- **ABC does not include** spread prestressed concrete or steel girder bridges with cast-in-place concrete decks; ABC must save a construction process, e.g., placing formwork for deck
- ABC does include adjacent beams, e.g., adjacent box beams
































7





	icated		5 — Misc. Element ninate various activities that are assort the use of PBES	-
	Misc. Structural Elements	 Precast Approach Slab Precast Curb Prefabricated Railing Precast Diaphragm Steel Diaphragm 	 LWC Beam (lightweight concrete beam) LWC Deck (lightweight concrete deck) LWC Substructure (lightweight concrete substructure) Other Miscellaneous Element 	
ABC	Closure Joints / Connections	 CIP Reinforced Closure Joint (cast-in-place reinforced concrete closure joint) High-Strength CIP Reinforced Closure Joint HESt-LSh Concrete Joint (high-early-strength low-shrinkage concrete joint) UHPC Closure Joint (ultra-high performance concrete closure joint) Epoxy Joint Grouted Key Closure Joint 	 Grouted Blockout w/ Shear Connector Grouted Duct Connection Pocket Connection Socket Connection Link Slab Match Cast Closure Joint Bars in Splice Coupler PT Ducts/Bonded PT Ducts/Un-bonded Other Closure Joint/Connection 	
(30/2021 Ref.: <u>https:/</u>	//abc-utc.	fiu.edu/resources/project-research-databases/project-datab	ase-keywords/	17

Γ






Structural Solutions – Prefab. Systems, cont'd., 2


• Prefabricated **superstructure systems** include both the deck and primary supporting members integrated such that mobility disruptions occur only as a result of the system being placed; these systems can be rolled, launched, slid, lifted, or otherwise transported into place as a unit onto existing or new abutments and/or piers


 FDcBc (Full-Width concrete-Decked concrete Beam Unit) FDcBs (Full-Width concrete-Decked steel Beam Unit) FDcBs (Full-Width concrete-Decked steel Beam Unit) Through-Girder Span w/Deck Truss Span w/Deck Arch Span w/Deck 	 Steel Orthotropic Box Girder Span Prestressed Multi-Cell Box Girder Span Metal Panel Deck Span RDcBc (Reused concrete-Decked concrete Beam span) RDcBs (Reused concrete-Decked steel Beam span) Other Superstructure System 	FDCBs Elk Creek Crossing 3
Steel Orthotropic Box Girder Span Maritime Off-Ramp		Truss Span w/Deck Willis Ave. over Harlem River 20


Structural Solutions – Prefab. Systems, cont'd., 3

- Examples of prefabricated **superstructure/substructure systems** are rigid frames that include either the interior piers or the abutments, or buried bridge systems, without foundations, and rolled, launched, slid, lifted, or otherwise transported into place as a unit onto existing or new foundations
- Prefabricated **total bridge systems** include the entire superstructure and substructure (both abutments and piers) on shallow foundations, made integral with the superstructure, built off-line and rolled, launched, slid, lifted, or otherwise transported into place as a unit on the existing alignment such that traffic operations can resume after placement










25

For more information on ABC technologies:

Accelerated Bridge Construction University Transportation Center (ABC-UTC)

https://abc-utc.fiu.edu





Implementing Accelerated Bridge Construction -A Rural State's perspective







Accelerated Bridge Program



Kristin Higgins, P.E. Vermont AOT Structures Program Manager Vermont State Bridge Engineer






Braintree – Gravel Road



1st ABC Project – Full Replacement

Construction Year: 2010 67' Prestressed Concrete Box Beams Precast Pile Caps and Wingwalls/14/2011 13:23 20-day bridge closure planned Low ADT




Braintree as Designed – Everything Precast






Chester Precast Abutment







East Montpelier – Precast steel Bridge Units (PBU's)



Early ABC Project Cost

- Braintree
 - Construction Cost:
 - Preliminary Engineering Cost:
 - Construction Engineering Cost:
- Chester
 - Construction Cost:
 - Preliminary Engineering Cost:
 - Construction Engineering Cost:
- East Montpelier
 - Construction Cost:
 - Preliminary Engineering Cost:
 - Construction Engineering Cost:





Setting the Stage for the Vermont's Accelerated Bridge Program


- Aging bridge population
- Dozens of Legacy projects
- We had done a couple already
- Massachusetts was a leader in ABC and was eager to assist
- Tropical Storm Irene (August 2011)






Accelerated Bridge Program Implementation

- Structures Section Reorganization in 2012
 - Accelerated Bridge Program (ABP) with dedicated leadership and staff was created
 - Project Initiation and Innovation Team with dedicated leadership and staff was created to scope project. ABC is always first option



15

Dedicated Accelerated Bridge Program Website



Accelerated Bridge Program - Brand





Shirts

Stickers

17




Act 153 – Town Highway Bridge Projects

2012: Legislation is passed to Promote ABC

- 50% Reduction in local share if the Town closes the bridge during construction
 - 5% local share for Bridge Replacement
 - 2.5% local share for Bridge Rehabilitation

% of Towns Taking Advantage of Act 153 Each Year



Road Closures in a Rural State

- Mitigate Isolation
 - Mutual emergency response aid from neighboring towns
 - Staged emergency services (EMT or Firetruck staged for response)
- Reduced response time Emergency Services
 - Difficult to navigate and can derail a project
- Ideal mitigation Identify unofficial bypass
 - Narrow and mountainous gravel Road
 - Neighborhoods
- Compensate for "damages" caused by increased traffic on local road network
- Establish realistic durations with I/D's clearly defined

Project Information

- AADT
- % Trucks
- Through Route Distance
- Detour Route Distance

Monetary Value of Travel time

- Median Household income
- Average Vehicle occupancy

Vehicle & Work zone Operating Costs

Discount Factor Approach

- Adjusted for Aggressiveness of closure period
- 1/2 of total incentive for meeting date
- 1/2 of total incentive used as hourly rate for early completion

Vermont P	r <mark>oject</mark>	Incentives	5
-----------	----------------------	------------	---

 Georgia Vermont – High ADT (Short Detour) 	\$103,000.00
 Moretown Vermont – Medium ADT (Long Detour) 	\$110,000.00
Mt. Holly Vermont – Low ADT Moderate Detour	\$47,040.00
 Plymouth Vermont – Low ADT Moderate Detour 	\$47,040.00
 Poultney Vermont – Low ADT (Short Detour) 	\$36,940.00
 Woodstock Vermont – Medium ADT (Aggressive Closure) 	\$66,000.00

21

Grants Available to Towns

Local Bypass Mitigation Grants

- Grants provided by the state to compensate towns for impacts to local roads due to increased traffic resulting from a state highway road closure
- The compensation amount is calculated based closure duration, traffic volumes, road classification and the bypass length and is intended to assist with:
 - Providing police presence to deter speeding
 - Providing enforcement to enforce local road weight limits
 - Dust control
 - Roadway maintenance (grading/addition of gravel/general maintenance)








Local Bypass Route on Municipally-Owned Roads: 1.0 Mile end-to-end


22



Precast Superstructure - Typical Section




Precast Integral Abutment





Short Span Structure (less than 50')



Precast Frame spans < 50'






Contractor Fabricated Elements


Contractor Fabrication

- Reduces dependency on subcontractors
- Maintain their workforce
- Greater availability to prefabricate/reduced costs
- Keeps heavy loads off state highways, no permits
- Required a new Specification



Superstructure - Alternates






31






Optioning for Means and Methods

_	BEGIN OPTION AA	
LS	PRECAST CONCRETE STRUCTURE (ABUTMENT #1)	540.10
LS	SPECIAL PROVISION (CONTRACTOR-FABRICATED PRECAST CONCRETE	900.645
	STRUCTURES)(ABUTMENT #1)	
	END OPTION AA	
	BEGIN OPTION BB	
LS	PRECAST CONCRETE STRUCTURE (ABUTMENT #2)	540.10
LS	SPECIAL PROVISION (CONTRACTOR-FABRICATED PRECAST CONCRETE	900.645
	STRUCTURES)(ABUTMENT #2)	- 1
	END OPTION BB	









Contract Language – Incentive/Disincentive

- <u>NOTICE TO BIDDERS INCENTIVE/DISINCENTIVE (I/D)</u>. The Agency's intent is to complete the Identified Work as rapidly as possible. To encourage the Contractor to complete the Identified Work within the period defined below, the Agency is willing to pay an incentive.
 - (a) <u>Dates</u>. The allowable I/D work period shall start at 7:00 a.m. and end 35 consecutive Calendar Days later by 6:59 a.m. This 35 consecutive Calendar Day work period is herein defined as the I/D Period. The Begin Construction Date for the I/D work period shall be determined by the Contractor. However, in no case shall the I/D work period begin before 7:00 a.m. on June 22, 2020, and it shall end no later than 6:59 a.m. on August 21, 2020.

The Contractor shall submit to the VTrans Construction Section for review and approval a certified letter specifying the Begin Construction Date for the I/D work. This letter shall be received by the Construction Section a minimum of 14 Calendar Days prior to the Begin Construction Date specified in the letter.

During the I/D Period, the Contractor will be allowed to work on the Project for 24 hours per day, 7 days per week, including holiday periods. Night work will be allowed during the I/D Period. See Special Provision No. 3 and No. 4 for additional information and requirements regarding night work.

The I/D Period as established above for this Contract is a fixed date and will not be changed for any reason whatsoever unless done so by the Secretary, and then only under extreme conditions as determined by, and at the sole discretion of, the Secretary. Contract Language – Identified Work within I/D Period

- (c) <u>Identified Work</u>. All work identified below shall be completed before the end of the I/D Period:
 - Wearing course of pavement placed on approaches;
 - Centerline of the approaches marked with line striping targets;
 - (3) Permanent bridge rail and approach guardrail; and
 - (4) Temporary pavement taper placed at bridge ends; and
 - (5) Transition barrier concrete achieves 85% design strength
 - (6) Detour signs removed or covered up.

All prefabricated concrete elements required to complete the Identified Work shall be authorized for shipment prior to the start of the I/D Period.

41

Contract Language – Pay Schedule for I/D Period

(d) <u>Pay Schedule</u>. The Contractor will receive a lump sum compensation of \$59,800.00 for completing the Identified Work before the end of the I/D Period.

In addition to the lump sum payment, the Contractor will also be compensated at a rate of \$300.00 per hour for each hour that the Identified Work is completed prior to the end of the I/D Period, up to a maximum total payment of \$103,000.00 (including the lump sum payment). Only full hours where the new bridge is opened by 6:59 a.m. will count toward this extra incentive payment.

For each hour after the end of the I/D Period that the Identified Work remains uncompleted, the Contractor will be assessed a disincentive at a rate of \$300.00 per hour. The full hourly disincentive amount will be assessed for each hour during which the Identified Work is not completed for any portion of the hour. There shall be no maximum on the disincentive amount.

This assessed disincentive is separate from, and will be imposed in addition to, liquidated damages which may be imposed for failure to complete the Contract on time.

Contract Language – Pre-I/D period meeting

(b) <u>Meetings</u>. There shall be a pre-I/D period meeting held on site with the Contractor's Superintendent, Contractor's Project Manager, the Engineer, the Project Manager, the Town of Georgia, Town of Georgia Fire Department, Georgia First Response, Vermont State Police, and the Northwest Regional Planning Commission (NRPC) to discuss durations of work, types of night work, work sequencing, etc. The Contractor shall be responsible for setting this meeting up and making appropriate contacts. This meeting shall be held a minimum of 14 Calendar Days prior to the start of the I/D Period.

For this Project, there shall also be a public information meeting prior to the start of the I/D Period. The Contractor's Superintendent and Contractor's Project Manager shall be available to attend. The Contractor shall be prepared to discuss the construction schedule with the public. The Public Outreach Coordinator shall be responsible for setting this meeting up and making appropriate contacts. This meeting shall be held a minimum of 21 Calendar Days prior to the start of the I/D Period.

Weekly meetings between the Contractor, Engineer, and other pertinent parties as determined by the Engineer shall be held during the I/D Period to discuss the Project progress and future construction activities, and current CPM progress schedules and narratives.

Contract Language – Traffic Control - Closure

Traffic Control


The contractor shall be responsible for the design and implementation of a specific traffic control plan for all stages of construction. The plan shall clearly detail how traffic will be maintained for each phase of construction. The plan shall clearly specify all construction activities for each phase and show appropriate temporary traffic control. All costs will be included in the item 641.11, Traffic Control, All inclusive".

Allowable work outside of closure

No daily lane closures will be allowed before 14 days prior to the BCP to progress work items outside EPSC and Traffic Control.


In the 14 days prior to the BCP the contractor will be allowed to maintain a minimum of one-lane (10 feet wide) alternating traffic for Pre-Excavation of Integral Abutment Piles, and pile driving operations during daytime hours. No night work will be allowed during this 14-day window and two-lane, two-way traffic must be maintained on the existing alignment during nighttime hours.

Accelerated Bridge Program




Accelerated Bridge Program

ABC Projects in Vermont







A State DOT's ABC Decision-Making Process



<u>Presenter</u>

Timothy D. Fields, P.E. Transportation Principal Engineer Division of Bridges - Major Structures Connecticut Department of Transportation







Connecticut Department of Transportation

Connecticut DOT's ABC Decision Process

- ABC Decision Matrix developed as a collaborative process with major assistance From Mike Culmo, P.E. with CHA Consulting, Inc.
- Development occurred over 3 year period
- Used on pilot basis during refinement prior to official release
- ABC Decision Matrix officially released November 2017 with mandate for use in CTDOT bridge design projects
- Now used in preliminary design of all bridge projects involving replacement of bridge deck, superstructure, and entire bridge

<section-header><section-header><section-header><section-header><list-item><list-item><list-item><list-item><section-header>


Implementation of ABC at CTDOT

- CTDOT understood the benefits of ABC
- But needed a decision process to use ABC wisely
 - Early ABC projects were successful, but expensive
 - Needed method to evaluate comparative costs and benefits of ABC for good project decision making



Building on work by others

- There were several ABC decision processes in use across the United States
 - Some simple (FHWA, Utah DOT)
 - Others more complex (Oregon: Analytical Hierarchy Process)
- Simple process
 - Easy to use
 - May not factor in all the desired aspects of the decision process (i.e. Cost)
- Complex Process
 - Provides a more detailed justification
 - Not justified at the decision process milestone (not all information is determined yet)
 - Too onerous



Econecticut Department of Transportation Project: 902-855 2000 Belin Turnyke, PD Boi 37848 Bar AH Checked: Wavefaco, CT GMIS/7848 Data: 217/2017 CTDOT ABC Decision Making Process 1 of 4 4	Department of Transportation Project: 803-285 2000 Belin Turnyke, PD Boi 37746 Ba AH Checked 0 Winstgor, CT 1081/27468 Date: 4 4 1 CTDDT ABC Decision Making Process 11-116 11-116 1 1	Connecticut Department of Transportation 2800 Berlin Turnpike, PO Box 317546 Newington, CT 06131-7846 CTDOT ABC Decision Making Proces	Project: 103-265 Bi: AH Checked: 0 Date:	Connecticut Department of Transportation 2800 Berlin Tumpike, PO Bos 37546 Newington, CT 06131-7846 CTDDT ABC Decision Making Process	Project 103-265 Bit AH Checked: 0 Date:
Size Advances and a second sec	Definition Control control control control Definition Control contro control control contententententententententententententen	ABC Basing procedure Between eraps Daily Traffi 1 Combined traffic on and under Combined traffic on and under Calculated by president Calculated by president Calculated by president Calculated by president Difference on the set State of Typical Deta 1 Detor guilty addit MPT Quality Bise of Typical Deta 1 Difference on the set Site Conditions 2 Bise of Difference on the set Bise of Typical Deta 1 Detor guilty addit MPT Quality addit Bise of Typical Deta 2 Bise of Typical Deta 3 Bise of Typical Deta 4 Difference on the set Bise of Typical Deta 4 Bise of	project. Altuch back-up data if applicable beta framework in the species center of the sp	Factor 25 Hardren 200 Hardren	View Match Failers (30%) Not / Failers (30%) Not / Failers (30%) Not / Failers (30%) Not / Failers (30%) View Not / Failers (30%) Social Failers (30%) Not / Failers (30%) Social Fa
Matrix calculatesOutput macro the	weighted ABC rating scores f in provides the user with an <i>l</i> ut in <u>yellow</u> boxes; Spreads	ABC rating sc sheet output i	ore.		ation

ABC Decision Matrix		<u>Site Information</u> Project De	escription:			
Sheet 1	CTDOT ABC	Prop. ABC	C Method:			
Enter Site Information data Project description ABC construction method Conventional Construction method 	Matrix Screen Shot	Conventio	onal Construction	n Method:		
Enter following traffic inputs for <i>Road</i> <i>Bridge</i> and <i>Roadway Below Bridge</i> (if applicable) for both <i>Conventional</i> and alternatives for determination of user reduction:	ABC	-	Construction I Aggregate Imp Delay Time (P	Per Delay Time Sheets Impact Duration pact Time Per Delay Time Sheets Impact Duration	0 Person Days	
 ADT Delay Time (entered from supplement traffic delay time spreadsheets) Construction Impact duration Spreadsheet calculates User Impact Reduces value for ABC compared to Conventional Construction 		-	Daily Traffic Dalay Time (P Construction I Construction I Aggregate Imp Delay Time (P Construction I Aggregate Imp	Per Delay Time Sheets Impact Duration pact Time Per Delay Time Sheets Impact Duration pact Time	Days 0 Person Days	
8	Conr	Conventio ABC	nal Construction Total Aggrega Total Aggrega act Reduction	n ate Impact Time ate Impact Time	0 Person Days 0 Person Days #DIV/01	

CTDOT Approach to User Impacts

- User costs
 - Some states calculate user costs
 - Good tool for political justification of ABC
 - Problem:
 - You cannot spend user costs (not a real cost to the DOT)
 - Approach to calculating user costs vary widely
 - What is important?
 - Impact of ABC on road users, environment, etc.
 - The ratio of impacts is more important than the
 \$\$





Connecticut Department of Transportation

CTDOT Approach to User Impacts

User cost impact ratio approach

- Compare aggregate road user impacts for ABC versus conventional construction
 - Calculated in person days
 - Add up impacts to travelers on the bridge
 and below the bridge
 - Calculate a percent increase or reduction
- Key factors needed
 - ADT for all roadways
 - Delay time for all roadways





Connecticut Department of Transportation

9

Weighted Factors

User Impact Reduction

- This value is a percent reduction of the time it takes for ABC construction compared to conventional construction.
- The spreadsheet calculates the appropriate value based on the input.
- Weight Factor: 30/108 (one of the highest weight factors)

Roadway on Bridge	User Impact Reduction 5 0 Zero
Average Daily Traffic vehicles per day Conventional Construction Delay Time (Per Delay Times Aperts) Aggregate Impact Duration Aggregate Impact Time 0 Person Days ABC Delay Time (Per Delay Time Sheets) Delay Time (Per Delay Times Apagregate Impact Time 0 Person Days	Calculated by spreadsheet 1 1% to 20% 2 21% to 40% 3 41% to 60% 4 61% to 80% 5 81% to 100%
Roadway Below Bridge Average Daily Traffic vehicles per day Conventional Construction Delay Time (Per Delay Time Sheets) minutes Aggregate impact Time 0 Person Days ABC Delay Time (Per Delay Time Sheets) minutes Construction Impact Duration Days Aggregate impact Time Sheets) ABC Person Days Delay Time Sheets) Person Days Person Days Days	CTDOT ABC Matrix Screen Shots
Percent Reduction in Aggregate Impact Time Conventional Construction Total Aggregate Impact Time 0 Person Days ABC Total Aggregate Impact Time 0 Person Days User Impact Reduction #DIV/00 Note: Negative value Indicated that ABC has more Impact	Connecticut Department of Transportation

	<u>User Imp</u>	act Ex	<u>ample</u>	
Site Information		Roadway on Bridge	Route 99	
Project Description:	Short span bridge replacement Bridge over a waterway	Average	Daily Traffic	7000 vehicles per day
Prop. ABC Method:		Conventio	onal Construction	
	Precast Integral Substructure		Delay Time (Per Delay Time Sheets)	3.00 minutes
	Modular Deck Beams Detour traffic		Construction Impact Duration	300 Days
			Aggregate Impact Time	4375 Person Days
Conventional Constru	ction Method: Staged construction One lane alternating traffic	ABC	Delay Time (Per Delay Time Sheets) Construction Impact Duration Aggregate Impact Time	8.00 minutes 30 Days 1167 Person Days
	Percent Reduction in Aggregate Impar Conventional Constructior Total Aggregate	1	4375 Person Days	2
	ABC Total Aggregate	e Impact Time	1167 Person Days	
		value indicated that AB0		CONNECTICUT E
12	CTDOT AB	C Matrix Screer Connectio	n Shots cut Department of Tran	sportation

CTDOT Approach to cost analysis

Ways to save \$\$ with ABC

- Reduced Construction Management Costs
 - Field Inspectors: Less time on the job
 - Backoffice staff: Reduced number of invoices and reports
 - Field office and equipment rental: Reduced number of months
- Reduced Traffic Management Costs
 - Temporary signals
 - Flagging and police
 - Multiple stages of construction
 - Elimination of Temporary Bridges
 - Elimination of overbuilds to accommodate construction stages





Connecticut Department of Transportation

ABC is less expensive than conventional

#DIV/0!


Net percentage of conventional cost =


Estimated conventional construction project cost = Required Bridge **ABC Decision Matrix** Overbuild Total conventional bridge cost Sheet 2 **Entire following project** Estimated CE&I Costs per month Field office monthly cost CE&I staff monthly cost (field plus main office) inputs: Total CE&I Monthly Cost = **Conventional Project Cost** Notes: Small field office = \$xxx per month Overbuild Medium office = \$xxx per month Large office = \$xxx per month Staff = \$20,000 per person per month Req'd base bridge costs CE&I Monthly costs **CTDOT ABC** Net time savings for ABC = months Field office Matrix Screen Estimated Percent Premium for ABC = CE&I staff Shot MPT savings with ABC ABC Net time savings Things that you can eliminate from conventional construction by using ABC
Overbuild for staging \$0 ABC estimated add'l cost Temporary bridge Temporary signal premium Other Total MPT Savings with ABC ¢. **MPT** (Maintenance & Protection of Traffic) cost savings with ABC Cost analysis Overbuild not needed Premium for ABC = Temporary bridge not needed \$0 Temporary signal not needed \$0 CEI Cost Savings = Other MPT savings with ABC = \$0 Spreadsheet calculates the ABC premium as a "Net Percentage of conventional Net cost change for ABC = \$0

cost"

14

13





Weighted Factors

Average Daily Traffic

- The goal of this measure is to account for the number of vehicles that are traversing the construction site. The value used should account for vehicles on the bridge and vehicles under the bridge (overpass structures).
- Weight Factor: 10/108







Bridge Location

- This is a measure of the location relative to the surrounding community and the impact on the economy when there is construction work on the bridge. A location that is vital to a connection to other transit would rate high in use of ABC. A location nearby a hospital would equally rate high.
- Weight Factor: 5/108


18


Bridge Location Stakeholder Impact	0 Rural Bridge away from town center 1 Rural bridge near town center 2 Suburban bridge away from town center 3 Suburban bridge near major traffic generators 4 Urban Bridge near major traffic generators 5 Urban Bridge near emergency services	
- Shall	CTDOT ABC Matrix Screen Shot	
- Spander	Connecticut Department of Transportation)





Weig	ghted Factors								
Site Conditions									
 This is a measure of site restrictions and how limited ROW or significant utilities impacts construction of the project. 									
 Numerous utilities could sev construction. 	Numerous utilities could severely influence the ability to use ABC construction								
 Restrictive ROW (e.g. building that cannot be acquired) prohibits the use of certain types of ABC construction like lateral slides, potentially SPMT moves or crane placement for prefabricated bridge units. 									
Weight Factor: 5/108									
Site Conditions Utilities/ROW/Env. Compliance	 significant limitations on work moderate construction limitations for portions of the work minor construction limitations 								
	5 No Restrictions								
CTDOT A	BC Matrix Screen Shot								
21	Connecticut Department of Transportation								










Cost Analysis

- This is comparative measure between the additional costs associated with ABC methodology related to the additional cost of conventional construction.
- The cost factor is generated from Sheet 2 and shown to the left of the input box.
- CTDOT is willing to spend a measured premium if other factors are high
- Weight Factor: 30/108 (one of the highest weight factors)







ABC Decision Matrix Rating Table

- ABC Rating table computes comparative rating for ABC project methodology under consideration
- Rating Table
 - Compiles all selected or computed rating measures
 - Multiples rating measures by weighting factors
 - Divides sum of weighted measure by theoretical maximum to produce ABC rating score
- Rating Scores
 - 60-100 Use ABC
 - 50-60 Consider ABC
 - 0-50 ABC not favorable

27

ABC Rating		Weight	Adjusted	Maximum	Adjusted
	Score	Factor	Score	Score	Score
Average Daily Traffic	0	10	0	5	50
User Impact Reduction	#DIV/0!	30	#DIV/0!	5	150
Bridge Location	0	5	0	5	25
Use of Typical Details	0	5	0	5	25
Work Zone Geometry	0	8	0	5	40
Site Conditions	0	5	0	5	25
Railroad Impacts	0	5	0	0	0
Cost Analysis	0	30	0	5	150
Envir. /Water Handling	0	5	0	0	0
Waterway Limitations	0	5	0	0	0
· · · · ·		Total Score	#DIV/0!	Max. Score	465
		ABC Rating	#DIV/0!	1	
		ADC Rating	#DIV/0:]	
		ABC Rating	Scale		
		60-100	Use ABC		
		50-60	Consider AE	BC	
		0-50	Do not use /	ABC	

CTDOT ABC Matrix Screen Shot

Connecticut Department of Transportation

Weighted Scoring Algorithm

- Score each measure on a scale of 1-5
- Weight factor provided for each measure considered
- Multiply score by weight factor
- Normalize the total to a scale of 1:100
- Why weight factors?
 - Some measures in the decision process are more important than others to the Department
 - Other agencies may vary weight factors depending on ABC goals and priorities

BC Rating	Score	Weight Factor	Adjusted Score	Maximum Score	Adjusted Score
Average Daily Traffic	3	10	30	5	50
User Impact Reduction	4	30	120	5	150
Bridge Location	4	5	20	5	25
Use of Typical Details	4	5	20	5	25
Work Zone Geometry	3	8	24	5	40
Site Conditions	3	5	15	5	25
Railroad Impacts	0	5	0	0	0 📛
Cost Analysis	4	30	120	5	150
Envir. /Water Handling	0	5	0	0	0 🧲
Waterway Limitations	0	5	0	0	0 📛
		Total Score	349	Max. Score	465
		ABC Rating	75]	
		ABC Rating			
			Use ABC	_	
			Consider AB	+	
		0-50	Do not use A	BC	

CTDOT ABC Matrix Screen Shot



ABC Decision Matrix Deployment

- Issued to all designers (in-house and consultants) on November 8, 2017
- Used in preliminary engineering phase for:
 - Deck replacement project
 - Superstructure replacement projects
 - Entire bridge replacement projects
- Not absolute

29


- It is an assessment tool, not a mandate
- Other factors can be considered (both positive and negative)
- ABC Decision Matrix Performance Good
 - A reasonable & reliable assessment tool


2	Connecticut DOT	Number:	EB-2017-6
9	Office of Engineering	Date:	November 8, 2017
	ENGINEERIN	G BULLETIN	G
24	Timezone H Hiteanna, H E WHT-11 all 1370 23-0010		

Accelerated Bridge Construction Decision Matrix

The Accelerated Bridge Construction (ABC) Decision Matrix is issued as a new Bridge Design Standard Practice. It shall be used to assess the vability of accelerated bridge restruction methodology alrange the performancy design phase of all projects involving bridge deck replacement, superstructure replacement or entire bridge replacement. The comparison Guide explains the use of the worksheet and definition of the input variables obtained from project preliminary design development. The results of the accelerated bridge construction assessment for any project should not be considered to the absolute as other factors not included in the decision matrix may be significant. However, accelerated bridge construction assessment for any point while do not be considered to where the results of the worksheet analysis are favorable for accelerated bridge construction. It is anticipated bridge construction. It is anticipated that the Accelerated Bridge Construction Matrix will be updated from time to ture as the Department's experience grows in this relatively new construction methodology.

The Accelerated Bridger Construction Decision Matrix and Guide are available via Bridge Standard Practices Tark on the Dission of Bridgers web page.






What is the issue or concern?


- A recent national poll of bridge owners discovered one common concern:
 - Negative feedback of ABC from the contracting community is holding back acceptance and wider implementation of ABC
 - The concerns being raised aren't technical in nature
- \$1.2B version of our next highway funding bill potentially gets voted on today
 - ABC should expect increased demand as the bill passes
 - This increased demand is better met with collaborative approaches to ABC





































			-						1		
ABC Components	703 O'Brien	106 Boone (Mackey Bridge)	106 Madison	305 Marion	508 Pottawattamie (CB 24 th)	208 Bremer	109 Buena Vista	210 Washington	111 Pottawattamie (Keg Creek)	L-#3973-90Wapello (Waffle Deck)	113 Cass (Massena)
Approach pavement	X		-			Х	1	Х	Х		
Abutment wings				-			Х		Х		X
Integral abutments	1	X	Х		· · · · · · · · · · · · · · · · · · ·	-	Х	-		1	
Semi-integral abutments									Х		X
Drilled shafts			1						Х	1	
Pile bents		X									
Frame piers									Х		
T-piers			0.05								
Box beams			Х				X				
PPCB + diaphragms		X			[]			1.000		Х	X
RSB + diaphragms			-								1.
Full depth precast deck	1	X	1		Х					Х	
Rails								-			
RSB + deck + rail					-				X		
Paving notch repair	-			X							
A + B contracting					Х						
Staged construction			-		X			-		-	
I/D contracting			-				X	-	X		X
Slide-in bridge constr.	-		-					-			X
UHPC	-		-	-		-	-		x	x	~
Post-Tensioning	-	x	-		x			-	~	^	
Grouted splice coupler	-	^	-		~			-	x		








Background: Iowa's ABC Program Other Key Projects
 2006: Mackey Bridge: Boone County, Precast substructure and full depth precast deck panels. 2006: Madison County Bridge, Precast abutment footings and precast box beams. 2008: 24th Street Bridge over I-80 in Council Bluffs, Precast Deck Panels, P/T, and grout pockets. 2011: US 6 over Keg Creek (Modular), PBES, UHPC, on-site prefabrication, I/D contracting, & drilled shafts. 2015: IA 92 over Little Silver Creek Bridge (Keg Creek 2.0), Improvements: S.S. deck rebar, smaller UHPC joints, & CIP alternatives. 2019-2021: Statewide County Bundling Project, 8 bridges, Precast Concrete Box, Precast Abutments, UHPC Joints.






































Accelerated Bridge Construction in Nebraska



NEBRASKA

Good Life. Great Journey.

DEPARTMENT OF TRANSPORTATION

Mark Traynowicz

Dale Burkhead Simon Contractors

Contractor/Owner Collaboration Workshop

September 30, 2021

Today's presentation

- Brief History of Accelerated Bridge Construction in Nebraska
- Nebraska's all Precast Bridge



History of ABC in Nebraska – How did we get here?

- Precast Concrete Deck Panels
- Steel Tubs
- Precast Elements
- Precast Approach Slabs
- Work closely with University of Nebraska
- Durable before Fast



Skyline Drive (Precast Concrete Deck Panels)



- Built in 2002
- Post-tensioning in Open Troughs
- Finished with Concrete Overlay



Phillips Interchange over I-80 (Steel Tubs)





- Built in 2003
- Simple to erect
- HPSW-100ksi
 - First in USA

262nd Street over I-80 (Steel Tubs)



- Built in 2008
- Headed Rebar
- Overnight Interstate Closure
- HPSW-70ksi

Primrose East (Folded Plate)



- Built in 2014
- Folded Plate Girders
- GRS Abutments
- Precast Elements



7

Primrose East (Folded Plate)



UHPC Connections



Kearney East Bypass (Precast Concrete Deck Panels)



- Built in 2016
- Full Width
- Tangent Roadway
- Post Tensioning under
 Precast Panels
- No Overlay



9

Belden to Laurel All Precast Bridge



ABC Precast Elements Bridge

- Single span 130'
- 43' wide
- 10 skew
- Construction in 2018
- Designed by NDOT Staff
- Design-Bid-Build
- 13 mile detour
- 45 Calendar days of road closure per contract
- \$3,750 Incentive/Disincentive per day
- Incentive capped at ten days



55 Precast Elements

- 7 NU 1100 Prestressed Girders (131 feet long)
- 22 Full-depth Deck Panels with Bridge Rail
- 2 Abutment Caps
- 2 Abutment Backwalls
- 4 Abutment Wingwalls
- 2 Grade Beam Caps
- 8 Approach Section Panels
- 8 Paving Section Panels
- Fabricated in Lincoln, NE
- 140 miles from project site



Field Cast Concrete for Connecting Precast Elements

- High Early Strength Concrete
 - 3,500 psi in 48 hours
- Self-Consolidating Concrete
 - 5,000 psi
- Ultra High-Performance Concrete
 - 12,000 psi in 4 days
 - 21,000 psi in 28 days



US-20 Closed May 29, 2018



Remove Existing Bridge, Drive Pipe Piles



High Water 4 times during Construction



200 Ton Crane to lift and Set Heavy Substructure



Set Abutment Caps




Place rebar and fill pockets with High Early-Strength Concrete





19

Girder Erection



Girder Camber 11" (anticipated 8.5")



Set Abutment Backwalls




Prepare and Set Wings and Grade Beam





23

Drive Sheet Piles



Set Deck Panels



Styrofoam for SCC Side forms

Shim Packs to set Elevations

25

Setting Deck Panels




Shear Connector Pockets with Vent Holes for SCC



Setting Deck Panels



Last Panel Set July 13 – Four Days to set Panels




Placing Self-Consolidating Concrete





Belden - Laurel



Placing Ultra High-Performance Concrete



Preparing Prior to Pour



Bridge Rail Connections - UHPC





Placing Ultra High-Performance Concrete



Precast Approach Panels



Last Precast Approach Panel set on July 24



Flowable Fill Under Panels

High Early Strength Concrete in Joints

Open to Traffic July 26, 2018



Observations & Lessons Learned

- Block outs for piles were hard to line up with the driven piling
 - Suggest bigger block outs
- Difficulty keeping workers that will put in the long hours for this ABC project
- The contractor's work area (ROW) sometimes was not large enough for the equipment and prefabricated pieces
- The communication on this project was key and went very well
 - Between contractor, bridge design, fabrication plant, and district
- NDOT's good relationship with the AGC, Nebraska Chapter

Observations & Lessons Learned


- Support from DOT Administration is Important
- Input and Communication between Contractor and DOT Before, During, and After Construction
- Durable Joints are Imperative for a long-lasting bridge
- Gain Knowledge from Research University of Nebraska
- Market Success to the Public


ABC Next Steps - UHPC Decked NU Prestressed Girders



Questions?






















































Contractor/Owner Collaboration on ABC Programs Workshop

Recommended Approach to Contractor Collaboration for ABC at the Program Level and the Project Level

Michael Culmo, PE Chief Bridge Engineer CHA Consulting, Inc.

September 30, 2021





Instituting an ABC Program


- This is not an engineering problem
- This is an organizational management problem
- In order to have a successful implementation of an ABC program we need to:
 - Use a business management approach



How to create a successful program


Start with "WHY"

- Best selling book by Sinek
- Ted Talk Series (check it out on youtube)
- Harley Davidson example
- Apple example
- <u>https://www.youtube.com/watch?v=VtvjbmoDx-I</u>
- We need to clearly define "WHY" we are using ABC and write it down
- Guiding Principle Statement
 - A simple short statement is preferred
- Everything that we do in an ABC program needs to be based on the "WHY"





How to create a successful program




The concept of the "Golden Circle"

- Every process needs to be based on the "WHY"
- The "WHATS" are the desired outcomes
- The "HOWS" are the processes to achieve the "WHATS"



Start with "WHY"

- WHY do we use ABC?
 - Fortunately, we have this stated this already
 - FHWA ABC Website (and virtually every ABC publications)
 - Improved safety for travelers and workers
 - Improved quality and durability
 - Reduced User Impacts (Time = \$\$)
 - Reduced environmental impacts
 - Reduced construction management costs
 - · Guiding Principle Statement: My idea
 - · Changing construction to better serve society
 - You can develop your own




5

"WHAT" do we want to accomplish with an ABC Program?

We need to get buy-in from all levels of the organization and our industry partners

- Internal (DOT)
 - Management
 - Design staff (including consultants)
 - Construction staff
- External
 - Political
 - Public involvement
 - Contractor buy-in








CHA

Why is "buy-in" important?

- If contractors push back...
 - They won't call the design office
 - They will call
 - DOT Construction office
 - DOT management
 - Political leaders
 - If everyone is not on board with the "WHY", the program can fall apart








"HOW" do we get there?

We know the "WHY" and the "WHAT", what about the "HOW"?

How do we obtain contractor buy-in?






Step 1: Internal DOT Buy-in

Upper management

- They need to be educated as to the benefits of ABC
- This can be done with facilitated workshops/meetings
 - Open discussion about the aspirations of the program
 - Understanding of the benefits
 - Learning and understanding the meaning of the Guiding Principle Statement
- Why is this important?
 - They need to be the flag bearers for external communications








9

Step 1: Internal DOT Buy-in

Design Staff

- They need to be educated as to the benefits of ABC
- This can be done with facilitated workshops/meetings
 - Open discussion about the aspirations of the program
 - Understanding of the benefits
 - Learning and understanding the meaning of the Guiding Principle Statement
- Training: How to design with ABC
- Why is this important?
 - We need to develop buildable and efficient designs





Step 1: Internal DOT Buy-in

Construction Staff


- They need to be educated as to the benefits of ABC
- This can be done with facilitated workshops/meetings
 - Open discussion about the aspirations of the program
 - Understanding of the benefits
 - Learning and understanding the meaning of the Guiding Principle Statement
- Construction Benefits
 - Safety, lower CEI costs, etc.
- Why is this important?
 - They are at the front line with the contractors



Step 2: External Buy-in

Political

- Politicians need to be educated as to the benefits of ABC
- Why is this important?
 - The public will contact them, and they listen
 - Happy travelers are happy voters
 - Politicians secure funding for projects







Step 2: External Buy-in


Use information from successful programs

• 2009 Utah DOT Survey


Stakeholder Overall Satisfaction with ABC Satisfaction Score (1 = not satisfied, 7 = very satisfied) 1 2 3 4 5 6 7 Score of 3 = 1.4% Score of 2 = 0.0% Score of 3 = 1.4% Score of 4 = 1.4% Score of 5 = 2.8% Score of 6 = 18.3% Score of 7 = 76.1% Score of 7 = 76.1% Note: Total of Scores 5 through 7 = 97.2%




Step 2: External Buy-in



Knowing that ABC reduces traffic congestion and road closures, but increases costs, do you favor or oppose UDOT continuing to use ABC to build bridges on its major highways?





2011 Utah DOT Survey



Step 2: External Buy-in

Public Involvement

- We need to educate the public about what we are doing and WHY we are doing it.
- Why is this important?
 - We often plan short-term increases in impacts for longterm reduction in impacts.
 - The public needs to know the big picture and why
 - Initially there will be a trust issue
 - They have driven for years through work zones
 - We are the butt of their jokes
 - A few successful ABC projects can turn that around fast



What


How

WHY



Step 2: External Buy-in

- Contractors
 - We need to educate contractors about what we are doing and WHY we are doing it.
 - Why is this important?
 - Given a chance, contractors will switch out precast concrete to CIP concrete





What

Why do Contractor's dislike ABC?

They like to pour concrete

- They are staffed and equipped for CIP concrete work
- · Precasting takes work away from their staff
- Potential loss of control over project production and schedule
- Risk:
 - · Working with new technologies
 - Risk = \$\$ = loss of bid advantages



17

How to engage the Contracting Community

Programmatic

- An agency can hold regular meetings with the contractor's associations
- Educate them about the "WHY" = Guiding Principle
- Benefits of ABC
 - · Less overhead: Do more with less staff
 - Safer work environment:
 - Shorter duration work zones
 - Building off site
 - · Benefits to the traveling public
 - Reduced user costs due to delays
 - Happy motorists = Happy voters = better political support for more highway construction



What can we do about this?



Start with "practice projects"

- Get everyone on the same page
- · Bid a few projects with more relaxed schedules
 - Make it clear the switching to CIP will not be allowed even if there is time
 - Build contractor familiarity with ABC without so much risk
 - At some time in the future, there will be projects with much tighter schedules where ABC will be necessary
 - Goal: Reduce risk on future projects through practice
 - This should be clearly communicated with....
 - DOT management at all levels
 - Politicians
 - The contracting community

CHA

What can we do about this?



Project Level

- Pre-bid conferences
 - Explain why ABC is being used
 - Both programmatic and project level
 - Go through the proposed details
 - Invite comments:
 - Live
 - Post conference
 - Make it clear that switching to CIP will not be allowed




How can we make ABC more palatable to contractors?

- · Relax schedules on early projects
 - But not too much
 - Reduces risk = lower bids
- Limit value of disincentives
 - Reduces risk = lower bids
- · Consider allowing self-performance of precasting
 - Require development of QA/QC processes
 - · Expected quality should be the same as a precast plant
 - Utah DOT has contractors obtain PCI "Precast" certification
 - Allows the contractor to keep work in-house
 - This has worked well in Utah



Conclusions


- Instituting an ABC program requires an organizational management approach
 - WHY → WHAT → HOW
 - WHY is the most important aspect
 - · Everything we do should be based on the WHY
- Need to engage multiple players
 - All levels of DOT
 - Politicians
 - Contractors
 - Public
 - Contractor engagement is important
 - Program level
 - Project Level




Questions?




















Iowa's ABC Case Study 100' single span to minimize the impacts on the adjacent ramps Only 4'- 5' between existing high abutment footing and the new abutment Semi-integral with a separate secant wall or a high abutment without a separate wall Competent rock approximately 30 feet below the grade of Grandview Avenue and 10 feet below U.S. 61 Use ABC methods for 8-week closure or reduce the working days as the ABC method



Iowa's ABC Case Study

- Superstructure options:
 - Lateral slide or SPMT methods:
 - Staging area nearby?
 - Construction over live traffic?
 - Modular superstructure :
 - Weight concerns?
 - Change to rolled steel I-beam
 - Full depth deck panels







Iowa's ABC Case Study

- Potential sequence:
 - Close Grand Ave
 - Partially construct new abutments
 - Partially construct secant/tangent walls
 - Remove existing superstructure (night closures)
 - Close US 61
 - Remove existing abutments
 - Complete abutments and walls
 - Erect superstructure prefabricated units
 - Open US 61
 - Complete remaining activities
 - Open Grand Ave





